

MINI POWER CONTROL SYSTEM



JAYCO proposed WIRING DIAGRAM 06-19-2013

Exact Location of Breakers not Critical
As long as Water Heater & A/C-RR are on
opposite phases of Line Voltage.

Program Options:
Relay Shed Order:

- Relay 1 - W/H
- Relay 2 - A/C-RR
- Relay 4 - A/C-FRT
- Relay 3 - A/C-MID

50A Service = Sleep Mode
Generator = Shed Limit 44 amps
5500W

